

MISSISSIPPI BOARD OF WATER COMMISSIONERS
ATTALA

B 2000 WATER WELL DRILLERS LOG
3-15-62

Date: 3-15, 1962, Driller: Smith & Presley County Attala
 (Name)

		Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>HD Herod</u> (Name)		<u>red clay</u>	<u>3</u>	<u>3</u>
<u>West Miss Rd</u> (Address)		<u>red sand</u>	<u>20</u>	<u>23</u>
(2) Location: <u>NE 1/4, SW 1/4, Sec 29 T16R7</u>		<u>red sand</u>		
<u>11</u> miles <u>North</u> , of <u>Kosciusko</u> (distance) (direction) (Nearest Town)		<u>Clay like mixture</u>	<u>5</u>	<u>28</u>
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)		<u>light yellow</u>		
(4) Purpose of Well: <u>domestic</u> (Domestic Irrigation Municipal, Industrial, Other)		<u>Clay almost</u>		
		<u>white</u>	<u>2</u>	<u>30</u>
		<u>yellow shale</u>		
		<u>about four in.</u>		
		<u>yellow white</u>		
		<u>Clay</u>	<u>8</u>	<u>38</u>
		<u>white sand with</u>		
		<u>Clay mixture</u>	<u>2</u>	<u>40</u>
		<u>white sand</u>		
		<u>black clay</u>		
		<u>mixture</u>	<u>28</u>	<u>68</u>
		<u>hard shale</u>	<u>3"</u>	
		<u>white sand</u>	<u>7</u>	<u>75</u>
		<u>hard shale</u>		
		<u>about</u>	<u>4"</u>	
		<u>white black</u>		
		<u>Clay mixture</u>	<u>15</u>	<u>90</u>
		<u>black clay</u>		
		<u>trace of sand</u>	<u>18</u>	<u>100</u>
		<u>hard sand</u>		
		<u>rock about</u>	<u>1 1/2</u>	<u>101 1/2</u>
		<u>black clay</u>	<u>7</u>	<u>108</u>
		<u>white sand</u>		
		<u>very good</u>		
		<u>gravel</u>	<u>9</u>	<u>117</u>


Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 117 feet.
- (3) Water level 65 feet below top of ground.
- (4) Cased to 107, Size 2
- (5) Screen: Size 1/4, Length 6
- (6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation

Why

Drillers Remarks:



(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.