

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

BENTON  
G 2023  
3/2/81

13-12-81  
date well completed

Wilson Well Co, Inc  
firm name

BENTON  
county well located

LANDOWNER: TERRY DAVIS

PO Box 301  
Holly Springs, Miss  
(mailing address)

WELL LOCATION:

sec. 13 T. 3 N. R. 1 E.  
7 miles W of Ashland  
(distance) (direction) (nearest town)

WELL PURPOSE: Home  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:


- (1) diameter (inches) 4
- (2) total depth (feet) 195
- (3) static water level (feet) 170 below top of ground.
- (4) casing Plastic, 185  
(material) (depth)  
4" (size) if telescope see back.
- (5) screen 10', 185  
(length) (depth to top)  
4" (size) PLASTIC (material)
- (6) pump 3/4, 8  
(HP) (yield gpm)  
electric (type power)
- (7) electric log NO  
(yes or no)

(organization running log)

(8) how well bottom plugged Plastic Cap

DRILLERS REMARKS:

| description of formations encountered | from | to  |
|---------------------------------------|------|-----|
| Red clay - Red Sand                   | 0    | 30  |
| Red Sand                              | 30   | 60  |
| Red Sand - White clay                 | 60   | 75  |
| White clay - red sand                 | 75   | 105 |
| Red Sand                              | 105  | 135 |
| White clay - White Sand               | 135  | 150 |
| White Sand                            | 150  | 195 |



DEPT. OF NATURAL RESOURCES  
BUREAU OF LAND & WATER RESOURCES

MAR 23 1981

RECEIVED