

BOLIVAR
B-33
4-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

*Bolivar
Calhoun*
CODED

Date: April 2, 19 66, Driller: Layne-Central Company County Calhoun
(Name)


(1) Owner of Land: <u>L. Westbrook & Son</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Drew, Mississippi</u> (Address)	Clay	18	18
(2) Location: <u>1/4, 1/4, Sec. 9 T25R5</u>	Fine black sand	4	22
<u>_____</u> miles <u>_____</u> of <u>Drew</u> (distance) (direction) (Nearest Town)	Fine black sand & clay	10	32
(3) Topography: <u>flat</u> (Hilly) (Flat) (Level)	Clay & sand	16	48
(4) Purpose of Well: <u>irrigation</u> (Domestic Irrigation Municipal, Industrial, Other)	Clay, coarse sand & pea gravel	4	52
	Coarse sand & pea gravel	30	82
	Gravel, coarse sand	24	106
	Bottomed out on rock		106

Information upon completion of well:

- (1) Diameter 16 inches.
- (2) Total Depth 106 feet.
- (3) Water Level 11 feet below top of ground.
- (4) Cased to 56', Size 16"
- (5) Screen: Size 16", Length 50'
- (6) Were any formations sealed against pollution?
_____ yes, no no.

If YES depth of formation _____
Why _____
Drillers Remarks: _____

CODED



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss