

BOLIVAR

MISSISSIPPI BOARD OF WATER COMMISSIONERS

E-31

5-4-59

WATER WELL DRILLERS LOG

11/24/65  
651  
CODED

Date: May 4, 1959, Driller: Layne-Central Company (Name)

(1) Owner of Land: Claude & Henry Hebert  
(Name)

Shelby, Mississippi  
(Address)

(2) Location: NE 1/4, NE 1/4, Sec. 1 T24R5

7 miles east of Shelby  
(distance) (direction) (Nearest Town)

(3) Topography: flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: irrigation  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	30	30
Fine sandy clay	12	42
Fine sand	5	47
Blue clay	8	55
Coarse sand	2	57
Blue clay	3	60
Clay balls & gravel	2	62
Coarse sand	43	105

CODED

Information upon completion of well:

(1) Diameter 16 inches.

(2) Total Depth 105 feet.

(3) Water Level 25' 2" feet below top of ground.

(4) Cased to 65', Size 16"

(5) Screen: Size 16", Length 40'

(6) Were any formations sealed against pollution?

no yes, no no.


If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_

2800 GPM.

Engine Drive.



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.