

**BOLIVAR**  
**F-78**  
**4-14-58**

MISSISSIPPI BOARD OF WATER COMMISSIONERS

**WATER WELL DRILLERS LOG**

10/8/65  
 TR 519

Date: April 14, 1958, Driller: Layne-Central Company (County Bolivar)

**CODED**

(1) Owner of Land: Welshans and Allen  
 (Name)  
Rosedale, Mississippi  
 (Address)

(2) Location: 1/4, 1/4, Sec. 27 T33R7,  
5 miles west of Pace  
 (distance) (direction) (Nearest Town)

(3) Topography: flat  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: irrigation  
 (Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Material Sand, Clay, Red Clay, Shell, etc.	Depth Feet	Depth Feet
Clay	8	8
Red clay	11	19
Medium blue sand	17	36
Coarse sand	16	52
Coarse sand & pea rock	30	82
Coarse red sand	14	92
Coarse sand, pea rock & lignite	26	122

Information upon completion of well:

(1) Diameter 16x12 inches.

(2) Total Depth 122 feet.

(3) Water Level 15'2" feet below top of ground.

(4) Cased to 70' Size 16"  
2' of 16" x 12" Swage

(5) Screen: Size 12", Length 50'.


(6) Were any formations sealed against pollution?  
no yes, no no.

**CODED**

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_  
2400 GPM.  
Electric power.



Well No.

(Use Back Side)