

CODED

CODED

Bolivar
F 116
9-67

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

9/12 1967 *Delta Well Supply Co* Bolivar  
 date well completed firm name county well located

LANDOWNER:  
*A. S. Spinkes*  
*RFD 1 - Rose Dale*  
(mailing address)

WELL LOCATION:  
NE SE sec. *21* T *23* N R *7* E W  
*6* miles *East* of *Rose Dale*  
(distance) (direction) (nearest town)


WELL PURPOSE: *Home*  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) *4 X 2*
- (2) total depth (feet) *932*
- (3) static water level (feet) *24* below top of ground.
- (4) casing *3/4" steel*  
(material) (depth)  
(size) If telescope see back.
- (5) screen *20 ft*, *9 1/2*  
(length) (depth to top)  
*3/4" stainless steel*  
(size) (material)
- (6) pump *18*  
(HP) (yield gpm)  
*Electric*  
(type power)
- (7) electric log (yes or no)
- (8) how well bottom plugged *BP Valve*

description of formations encountered	from	to
<i>Clay</i>	<i>0</i>	<i>25</i>
<i>F. sand</i>	<i>25</i>	<i>45</i>
<i>Sandy gravel</i>	<i>45</i>	<i>110</i>
<i>Rock</i>	<i>110</i>	<i>111</i>
<i>C. sand</i>	<i>111</i>	<i>130</i>
<i>Clay</i>	<i>130</i>	<i>195</i>
<i>Rock</i>	<i>195</i>	<i>197</i>
<i>Clay</i>	<i>197</i>	<i>290</i>
<i>Shale</i>	<i>290</i>	<i>300</i>
<i>Clay</i>	<i>300</i>	<i>325</i>
<i>Sand</i>	<i>325</i>	<i>340</i>
<i>Clay</i>	<i>340</i>	<i>445</i>
<i>Sand M.</i>	<i>445</i>	<i>465</i>
<i>Clay</i>	<i>465</i>	<i>480</i>
<i>Sand hard F</i>	<i>480</i>	<i>490</i>
<i>Sand Clay shale</i>	<i>490</i>	<i>890</i>
<i>Sand</i>	<i>890</i>	<i>933</i>
<i>Shale</i>	<i>933</i>	<i>P</i>

CODED



DRILLERS REMARKS: