

Bolivar  
~~June 23~~ 31  
 6-23-81

**WATER RESOURCES**

Water Resources  
 Southport Mall  
 P.O. Box 10631

Jackson, Mississippi 39209  
**WATER WELL DRILLERS LOG CODED**

June 23 19 81 *Irrigation Well* Bolivar  
 date well completed firm name county well located

**LANDOWNER:**  
 CALVIN WARD  
 BENOT, MS 38725  
 (mailing address)

**WELL LOCATION:**  
 sec. 16 T. 22N R. 8 E  
 3 1/2 miles *N* of Benot  
 (distance) (direction) (nearest town)

description of formations encountered	from	to
TOP SOIL CLAY	0	10
CLAY	10	20
CLAY FINE SAND	20	30
" "	30	40
" "	40	50
COARSE SAND	50	60
COARSE SAND - GRAVEL	60	70
" "	70	80
" "	80	90
" "	90	100
" "	100	110

**WELL PURPOSE:** *Irrigation*  
 (home, irrigation, municipal, industrial)

**WELL COMPLETION DATA:**

(1) diameter (Inches) 10"

(2) total depth (feet) 110'

(3) static water level (feet) 25' below top of ground.

(4) casing PVC, 70'  
 (material) (depth)  
 (size) if telescope see back.

(5) screen 40, 70'-110'  
 (length) (depth to top)  
10", PVC  
 (size) (material)


(6) pump 2.5, 1200  
 (HP) (yield gpm)  
ELECTRIC  
 (type power)

(7) electric log NO  
 (yes or no)

(organization running log)

(8) how well bottom plugged PVC CAP

**CODED**



**DRILLERS REMARKS:**