

MISSISSIPPI BOARD OF WATER CONTROL DISTRICTS


WATER WELL DRILLERS LOG

Date: 10-27, 1966, Driller: Butane Gas Co. County Bolivar
(Name)

Bolivar
L 138
10-66

CODED

(1) Owner of Land: <u>Roy Griffin</u> <small>(Name)</small>	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Cleveland, Miss.</u> <small>(Address)</small>	Clay	8	8
(2) Location: <u>SE 1/4, NW 1/4, Sec. 13 22ⁿ 6^w R</u>	Sand	84	92
<u>3</u> miles <u>W</u> of <u>Cleveland</u> <small>(distance) (direction) (Nearest Town)</small>	Gravel	67	159
(3) Topography: <u>Flat</u> <small>(Hilly) (Flat) (Level)</small>	Clay	41	200
(4) Purpose of Well: <u>Domestic</u> <small>(Domestic Irrigation Municipal, Industrial, Other)</small>	Sand streak	132	332
Information upon completion of well:	Clay	2	334
(1) Diameter <u>4 3/4</u> inches.	Sand & Shale	114	448
(2) Total Depth <u>776</u> feet.	Sand & Shale Streaks	64	512
(3) Water Level <u>27' 8"</u> feet below top of ground.	Sand	69	581
(4) Cased to <u>755</u> , Size <u>4" X 2"</u>	Clay	58	633
(5) Screen: Size <u>2"</u> , Length <u>20'</u>	Sand & Shale	56	689
(6) Were any formations sealed against pollution? <u>yes</u> , <u>X</u> no.	Sand & Shale Streaks	42	731
If YES depth of formation _____	Shale	4	735
Why _____	Sand	20	755
Drillers Remarks: _____	Clay	21	776



Well No.

Retain this copy for your office files.

(Use Back Side)