

CODED

CODED

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

Bolivar
H M 144
1-67

1/23 1967 Duttwindle Supply Co Bolivar
 date well completed firm name county well located

LANDOWNER:
Leady Pruitt
RFD Cleveland
 (mailing address)

WELL LOCATION:
 sec. 6 T 23 N R 5 E
3 miles W-W of Cleveland
 (distance) (direction) (nearest town)

WELL PURPOSE: Home
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4 1/2

(2) total depth (feet) 765

(3) static water level (feet) 22 below above top of ground.

(4) casing 745 (material) (depth)
 (size) if telescope see back.

(5) screen 20 ft 745 (length) (depth to top)
2 (size) S.S. (material)


(6) pump 1 1/2 875 (HP) (yield gph)
elec (type power)

(7) electric log No (yes or no)
 (organization running log)

(8) how well bottom plugged
S.P. Tubing

description of formations encountered	from to	
<u>Top</u>	<u>0</u>	<u>15</u>
<u>Fine sand</u>	<u>15</u>	<u>45</u>
<u>Scarcely sand</u>	<u>45</u>	<u>120</u>
<u>Clay</u>	<u>120</u>	<u>125</u>
<u>Rock</u>	<u>125</u>	<u>126</u>
<u>Shale</u>	<u>126</u>	<u>190</u>
<u>Sand</u>	<u>190</u>	<u>205</u>
<u>shale</u>	<u>205</u>	<u>268</u>
<u>Rock</u>	<u>268</u>	<u>269</u>
<u>shale</u>	<u>269</u>	<u>260</u>
<u>fine sand</u>	<u>260</u>	<u>430</u>
<u>Clay</u>	<u>430</u>	<u>435</u>
<u>W sand</u>	<u>435</u>	<u>500</u>
<u>Shale</u>	<u>500</u>	<u>620</u>
<u>Fine sand</u>	<u>620</u>	<u>700</u>
<u>Hard shale</u>	<u>700</u>	<u>720</u>
<u>Sand</u>	<u>720</u>	<u>770</u>
<u>Clay</u>	<u>770</u>	<u>865</u>

CODED



DRILLERS REMARKS: