

BOLIVAR MISSISSIPPI BOARD OF WATER COMMISSIONERS

R N 44

4-25-64

WATER WELL DRILLERS LOG

6757

Date: April 25, 1964, Driller: Layne-Central Company County Bolivar (Name)

(1) Owner of Land: Delta & Pine Land Co.
Myers Plantation
Scott, Mississippi
 (Address)

(2) Location: 1/4, 1/4, Sec. 12 T21N R8W
_____ miles _____ of Scott
 (distance) (direction) (Nearest Town)

(3) Topography: flat
 (Hilly) (Flat) (Level)

(4) Purpose of Well: domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Top soil	15	15
Blue clay balls	57	72
Coarse sand, gravel	53	125
Blue clay	12	137
Rock	1	138
Blue clay	151	289
Sandy shale	62	351
White rock sand	16	367
Gummy blue clay	33	400
Sandy shale	15	415
Blue gummy clay	30	445
Sandy shale	11	456
White rock sand	19	475
Sandy shale	98	573
White rock sand	33	606
Clay	3	609

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 609 feet.

(3) Water Level 31' - 5" feet below top of ground.

(4) Cased to 574' - 2", Size 4"


(5) Screen: Size 4", Length 30' - 10"
4' of 4" B.P.V.

(6) Were any formations sealed against pollution?
yes yes, _____ no.

If YES depth of formation Packer above the screen; mechanical seal at bottom.
 Why _____

Drillers Remarks: _____

CODED



Well No. _____

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.