

BOLIVAR

MISSISSIPPI BOARD OF WATER COMMISSIONERS

Coded CODED

R N 50


2-21-62

WATER WELL DRILLERS LOG

3/14/62

Date: Feb. 21, 1962, Driller: Layne-Central Company Bolivar (Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>Delta & Pine Land Co.</u> <u>Eutaw Plantation</u> <u>Scott, Mississippi</u> (Address)	Clay	3	3
(2) Location: <u>1/4</u> , <u>1/4</u> , Sec. <u>21</u> T <u>21</u> N R <u>9</u> W	Fine silty sand	29	32
<u>5</u> miles <u>west</u> of <u>Scott</u> (distance) (direction) (Nearest Town)	Fine sand	25	57
(3) Topography: <u>flat</u> (Hilly) (Flat) (Level)	Coarse sand	11	68
(4) Purpose of Well: <u>irrigation</u> (Domestic Irrigation Municipal, Industrial, Other)	Pea gravel	27	95
Information upon completion of well:	Big boulders	5	100
(1) Diameter <u>16</u> inches.	Clay		100
(2) Total Depth <u>100</u> feet.	CODED		
(3) Water Level <u>5' - 8"</u> feet below top of ground.			
(4) Cased to <u>60'</u> , Size <u>16"</u>			
(5) Screen: Size <u>16"</u> , Length <u>40'</u>			
(6) Were any formations sealed against pollution? <u>no</u> yes, <u>no</u> no.			
If YES depth of formation _____			
Why _____			
Drillers Remarks: _____			



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss