

Bolivar  
P 90  
12-66

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

date well completed 12-20-66 firm name Butane Gas Co. of Greenwood county well located Bolivar

LANDOWNER:  
O.W. Williams

Rt. 1 Boyle  
(mailing address)

WELL LOCATION:  
sec. 15 T 21 N R. 6 W  
2 1/2 miles S of Stone  
(distance) (direction) (nearest town)

WELL PURPOSE: Home  
(home, irrigation, municipal, industrial)


WELL COMPLETION DATA:

- (1) diameter (inches) 4 3/4
- (2) total depth (feet) 1020
- (3) static water level (feet) 16 below top of ground.
- (4) casing Steel 966 (material) (depth)  
2" (size) if telescope see back.
- (5) screen 20' 966 (length) (depth to top)  
2" Stainless Steel (size) (material)
- (6) pump 1 13 (HP) (yield gpm)  
Elec. (type power)
- (7) electric log No (yes or no)  
(organization running log)
- (8) how well bottom plugged BRASS  
Basic Wash Valve

description of formations encountered	from	to
CLAY	0	18
SAND & GRAVEL	18	160
CLAY	160	250
SHALE	250	300
SAND	300	350
SAND & SHALE	350	400
CLAY	400	508
SAND	508	570
SAND & SHALE	570	740
CLAY	740	780
FINE SAND	780	960
WHITE SAND	960	1020

CODED

CODED



DRILLERS REMARKS: