

Bolivar MISSISSIPPI BOARD OF WATER COMMISSIONERS

R 42

3-66

WATER WELL DRILLERS LOG

**CODED**

Date: 3-22, 1966, Driller: Five County Farmers Assoc County: Coahoma  
(Name)

(1) Owner of Land: DELTA PINELAND CO  
(Name)  
SCOTT MISS  
(Address)

(2) Location: 1/4, 1/4, Sec. 11 T20R9  
2 1/2 miles West of SCOTT  
(distance) (direction) (Nearest Town)

(3) Topography: flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: IRRIGATION  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	14	14
Dry Red Sand	6 1/2	20 1/2
Mucky Grey Sand	13	33 1/2
Red Sand	19 1/2	53
Coarse Sand	26	79
Sand & Gravel	26	105

Information upon completion of well:

(1) Diameter 6 inches.

(2) Total Depth 101' 4" feet.

(3) Water Level 16 feet below top of ground.

(4) Cased to 53' 4", Size 6"

(5) Screen: Size 6", Length 48"


(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, \_\_\_\_\_ no.

**CODED**

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks:  
Driller Daugherty



(Use Back Side)

Well No. 3

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.