

BOLIVAR MISSISSIPPI BOARD OF WATER COMMISSIONERS *coded 3*


R 73
10-2-64 *12285* **WATER WELL DRILLERS LOG**

10/9/1964
CODED 14

Date: Oct. 2, 1964, Driller: Layne-Central Company County Bolivar - *R73*

(Name)

(1) Owner of Land: <u>Lamont Water Corporation</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Lamont, Mississippi</u> (Address)	<u>Sandy clay</u>	<u>12</u>	<u>12</u>
	<u>Blue clay</u>	<u>5</u>	<u>17</u>
(2) Location: <u>1/4, 1/4, Sec. 37 T20N R9W</u>	<u>Fine sand</u>	<u>22</u>	<u>39</u>
<u>1/4</u> miles, of <u>Lamont</u> (distance) (direction) (Nearest Town)	<u>Coarse sand & pea gravel</u>	<u>82</u>	<u>121</u>
(3) Topography: <u>flat</u> (Hilly) (Flat) (Level)	<u>Blue clay</u>	<u>33</u>	<u>154</u>
(4) Purpose of Well: <u>domestic</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>Hard white clay</u>	<u>3</u>	<u>157</u>
Information upon completion of well:	<u>Clay</u> <i>CODED</i>	<u>30</u>	<u>187</u>
(1) Diameter <u>8 1/4</u> inches.	<u>Fine sand</u>	<u>14</u>	<u>201</u>
(2) Total Depth <u>490</u> feet.	<u>Clay</u>	<u>54</u>	<u>255</u>
(3) Water Level <u>47</u> feet below top of ground.	<u>Clay with sandy strks.</u>	<u>23</u>	<u>278</u>
(4) Cased to <u>175'</u> , Size <u>8"</u>	<u>Sand & clay strks.</u>	<u>15</u>	<u>293</u>
(5) Screen: Size <u>4"</u> , Length <u>40' 4"</u>	<u>Clay with small sand strks.</u>	<u>65</u>	<u>358</u>
(6) Were any formations sealed against pollution?	<u>Sand</u>	<u>11</u>	<u>369</u>
<u>yes</u> yes, <u>no</u> no.	<u>Sandy clay</u>	<u>43</u>	<u>412</u>
If YES depth of formation <u>Mechanical seal,</u>	<u>Clay with sandy strks.</u>	<u>23</u>	<u>435</u>
packer above screen and B.P.V. at bottom.	<u>Sand with small shale strks.</u>	<u>57</u>	<u>492</u>
Why _____	<u>Fine sand with brown shale</u>	<u>68</u>	<u>560</u>
Drillers Remarks: _____	<u>Clay</u>	<u>33</u>	<u>563</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____



Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.