

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
Office of Land and Water Resources

P. O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

COUNTY WELL LOCATED
CALHOUN

WELL NUMBER **3** CODED

C-53

DATE WELL COMPLETED
9-18-2000

PERMIT NUMBER
GW 15828

NAME OF DRILLING FIRM
PARKS + PARKS WELL SERVICE

NAME & MAILING ADDRESS OF LANDOWNER
CITY OF BRUCE

BRUCE, MS

Latitude:
Longitude:

WELL LOCATION. SEC **36** TOWNSHIP **12 N** RANGE **2 E**

DISTANCE **1/8** Miles DIRECTION **W** of NEAREST TOWN **BRUCE**

OTHER LANDMARK

WELL PURPOSE: Home, Irrigation, Municipal, Industrial, Fish Pond, etc.

PUMP DATA

PUMP TYPE (Circle One):
Submersible, **Turbine**, Jet, Flowing Well,
Other (Describe)

POWER TYPE (Circle One):
Electric, Tractor, Diesel, Gasoline, Butane,
Other (Describe) **100** H/P

DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO
CLAY	0	58
CLAY + LIQUITE	58	88
CLAY	88	426
CLAY + SHELL	426	641
CLAY	641	958
CLAY + SAND	958	989
CLAY	989	1234
CLAY + SHELL	1234	1457
SAND	1457	1480
CLAY + SHELL	1480	1694
FINE SAND	1694	1756
GRAVEL	1756	1787
CLAY	1787	1871
GRAVEL	1871	1975
HARD GRAVEL	1975	2002
CLAY	2002	2074

RECEIVED

FEB 5 2002

BY: OLWR
GORDO Guter

Top of Lap Pipe or Reduction in Casing
1825 FEET IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE

WELL DATA

Well Depth 1975	Casing Diameter (In.) 12 3/4	Casing Length (Ft.) 1880
Type of Casing STEEL	Hole Depth 2075	Depth to Static Water Level 130.20


TYPE OF COMPLETION: (Circle One or More):
Gravel Packed, **Underreamed**, Telescoped,
Natural Development, Open Hole, Other
(Describe)

WELL GROUTED TO A DEPTH OF **1880** FEET
Type Grout (circle one): **Cement**, Bentonite, or Mix

SCREEN DATA

Diameter - Inches 8	Length - Feet 90	Slot Size - Inches .030
Screen Type S.S.	Depth to Bottom - Feet 1975	

I certify that the well was drilled, constructed and completed in accordance with all applicable Requirements of the Mississippi Department of Environmental Quality and/or the Mississippi Department of Health regulations and state laws.


Signature of Licensed Driller and License No.

1/30/02
Date

Additional Information Required On Back