

CARROLL MISSISSIPPI BOARD OF WATER COMMISSIONERS

E 24
7-7-60

WATER WELL DRILLERS LOG **CODED**

Date: JULY 7, 1960, Driller: DELTA DRILLING Co County: CARROLL
LEELORE

(Name)

(1) Owner of Land: J. M. STANFORD
(Name)

CARROLLTON MISS.
(Address)

(2) Location: 1/4, 1/4, Sec. 9 MR 3

 miles , of
(distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials
Sand, Clay, Red Clay, Shell, etc.

Thick-
ness
Feet


Depth
Feet

| | | |
|------------------|----|-----|
| CLAY | 16 | 16' |
| SAND w/ 3" ROCK | 48 | 64 |
| CLAY + SHALE | 21 | 85 |
| GUMBO | 11 | 96 |
| SAND | 33 | 129 |
| GUMBO w/ 8" ROCK | 84 | 213 |
| SHALE | 65 | 278 |
| SAND - GREEN | 92 | 370 |

Information upon completion of well:

- (1) Diameter 4 inches.
- (2) Total Depth 370 feet.
- (3) Water Level 99 feet below top of ground.
- (4) Cased to 370, Size 4" - 210'
2" - 150'
- (5) Screen: Size 2", Length 10'
10'-2" TAIL PIPE - EXTENDED TO 381'
- (6) Were any formations sealed against pollution?
 yes, no.

CODED



If YES depth of formation

Why

Drillers Remarks: 3/4 H.P. Red Jacket

SUBMERSIBLE PUMP SET 147'

IN WELL

Well No.

(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss