

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
Office of Land and Water Resources

P. O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

COUNTY WELL LOCATED CARROLL	
WELL NUMBER G-67	CODED
DATE WELL COMPLETED 6-1-01	

PERMIT NUMBER GW 16645
NAME OF DRILLING FIRM PARKS + PARKS WELL SERVICE
HOUSTON, MS 38807

NAME & MAILING ADDRESS OF LANDOWNER PELUCIA WATER ASSN RT 1 BOX 216 GREENWOOD, MS. 38930	
Latitude: Longitude:	
WELL LOCATION	SEC TOWNSHIP RANGE 27 18^N 2^E
DISTANCE	DIRECTION NEAREST TOWN 10 Miles S-SE of GREENWOOD
OTHER LANDMARK	
WELL PURPOSE: Home, Irrigation, Municipal, Industrial, Fish Pond, etc. RURAL WATER	


PUMP DATA		
PUMP TYPE (Circle One): Submersible, <u>Turbine</u> , Jet, Flowing Well, Other (Describe)		
POWER TYPE (Circle One): <u>Electric</u> , Tractor, Diesel, Gasoline, Butane, Other (Describe) <u>50</u> H/P		
DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO
CLAY + SAND	0	58
RED SAND	58	89
GRAVEL	89	160
CLAY	150	273
CLAY + SAND	273	378
HARD SAND	378	491
SAND + SHELL	491	553
SAND	553	615
SAND + CLAY	615	677
SAND	677	798
HARD SAND	798	845

WELL DATA		
Well Depth 910	Casing Diameter (In.) 12 3/4	Casing Length (Ft.) 845
Type of Casing STEEL	Hole Depth 950	Depth to Static Water Level 157
TYPE OF COMPLETION: (Circle One or More): <u>Gravel Packed</u> , <u>Underreamed</u> , Telescoped, Natural Development, Open Hole, Other (Describe)		
WELL GROUTED TO A DEPTH OF 845 FEET Type Grout (circle one): <u>Cement</u> , Bentonite, or Mix		

SCREEN DATA		
Diameter - Inches 6	Length - Feet 60	Slot Size - Inches .016
Screen Type S S	Depth to Bottom - Feet 910	

RECEIVED
FEB 15 2002
BY: OLWR
Top of Lap Pipe or Reduction in Casing
790 FEET IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE

I certify that the well was drilled, constructed and completed in accordance with all applicable Requirements of the Mississippi Department of Environmental Quality and/or the Mississippi Department of Health regulations and state laws.


Signature of Licensed Driller and License No.

9/18/2000
Date

Additional Information Required On Back