

Carroll
K 8
3-67

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

3-27 1967 Jack Martin Carroll
date well completed firm name county well located

LANDOWNER: William Barrett
Hilsmichael
(mailing address)

description of formations encountered

from to

WELL LOCATION:
sec. 27 T. 18 N. R. 6 E
1 miles NE of Vaiden
(distance) (direction) (nearest town)


Clay	0	8
pipe	8	20
Sand	20	29
Mud	29	32
Sand & pipe clay	32	38
Coarse Sand	38	62
Mud - Sand streaks	62	84
Sand	84	89
Sand & Mud	89	108
Rock layers & mud	108	112
Mud	112	118
Sand	118	128
Mud	128	152
Mud & Sand	152	156
Sand	156	172
Mud & S. Streaks	172	230
Sand	230	248
Mud - Rock layers	248	254
Sand	254	268
Mud	268	312
Mucky sand	312	339
Mud	339	362
Sand	362	368
Mud	368	386
Mud & Sand	386	394
Sand	394	436

CODED

WELL PURPOSE: Subdivision
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (Inches) 4" x 2 1/2"
- (2) total depth (feet) _____
- (3) static water level (feet) 66 below top of ground.
- (4) casing Steel (material), _____ (depth),
4 x 2 1/2 (size) if telescope see back.
- (5) screen 30 (length), 40 (depth to top),
2 (size), Stainless Steel (material)
- (6) pump 5 (HP), 70 (yield gpm),
Electric (type power)
- (7) electric log no (yes or no),
Organization running log
- (8) how well bottom plugged 2" Cap



DRILLERS REMARKS: