

CARROLL

MISSISSIPPI BOARD OF WATER COMMISSIONERS

02
2-8-63


MS-GW-02162
WATER WELL DRILLERS

CODED

CARROLL

Date: 2-8-63, 1963, Driller: Carloss Well Supply County: ~~Stacy~~

(Name)

(1) Owner of Land: <u>Town of Vaiden</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Vaiden, Mississippi</u> (Address)	Red Sandy Clay	15	15
<u>Water Plant</u>	Blue Shale	10	25
(2) Location: <u>1/4, 1/4, Sec. 23 T. 12 R. 5</u>	Fine Green Sand w/ Streaks of Clay	30	55
<u> </u> miles, of <u> </u> (distance) (direction) (Nearest Town)	Coarse Green Sand w/ Streaks Clay	26	81
(3) Topography: <u>X</u> (Hilly) (Flat) (Level)	Brown Clay	5	86
(4) Purpose of Well: <u>Municipal</u> (Domestic Irrigation Municipal, Industrial, Other)	Green Sand	17	103
Information upon completion of well:	Yellow Clay	10	113
(1) Diameter <u>12</u> inches.	White Sand	83	196
(2) Total Depth <u>196</u> feet.	Hard Shale	1	197
(3) Water Level <u>71</u> feet below top of ground.	Fine White Sand	7	204
(4) Cased to <u>155'</u> , Size <u>12"</u>	Shale	2	206
(5) Screen: Size <u>8"</u> , Length <u>40'</u>	Rock	1	207
(6) Were any formations sealed against pollution? <u>X</u> yes, <u> </u> no. Cemented	CODED		
If YES depth of formation <u> </u>			
Why <u> </u>			
Drillers Remarks: <u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			
<u> </u>			

Well No.

(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss