

F5

MSGW = 01236 (per P.F.P. 1/16/63)

CHOCTAW MISSISSIPPI BOARD OF WATER COMMISSIONERS

CODED

F5 WATER WELL DRILLERS LOG

Date: April 7, 1961, Driller: Layne-Central Company County Choctaw

(Name)

(1) Owner of Land: French Camp Academy (Name)

French Camp, Mississippi (Address)

(2) Location: 1/4, 3 1/4, Sec. 17 9 T R

miles near of Weir (distance) (direction) (Nearest Town)

(3) Topography: hilly (Hilly) (Flat) (Level)

(4) Purpose of Well: domestic (Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	26	26
Fine sand	6	32
Hard clay	11	43
Shale	39	82
Sandy shale	28	110
Sand	105	215
Sand shale	47	262
Sand	11	273
Sandy shale	12	285
Shale, hard brittle	345	630
Pack, sand gray	63	693

Information upon completion of well:

(1) Diameter 4x6 inches.

(2) Total Depth 693 feet.

(3) Water Level 82 feet below top of ground.

(4) Cased to 647', Size 6"

(5) Screen: Size 40', Length 4"


(6) Were any formations sealed against pollution?

X yes, no.

If YES depth of formation 4x6 lead seal.

Why to eliminate all other formations.

Drillers Remarks:



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson. Miss