

CHOCTAW MISSISSIPPI BOARD OF WATER COMMISSIONERS

G 16


WATER WELL DRILLERS LOG CODED

1-31-63

Date: 1-31, 1963, Driller: J.L. MERRAT County CHOCTAW

(Name)

(1) Owner of Land:	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
ALVIN EARLES (Name)	Red SAND & CLAY	0	16'
ACKERMAN, MISS (Address)	SAND ROCK	16	17
(2) Location: 1/4, 22, 17 10, Sec. T R	Red CLAY	17	35
5 miles WEST, of ACKERMAN (distance) (direction) (Nearest Town)	LIGNITE	35	40
(3) Topography: HILL (Hilly) (Flat) (Level)	Blue CLAY	40	70
(4) Purpose of Well: DOMESTIC (Domestic Irrigation, Municipal, Industrial, Other)	LIGNITE	70	75
Information upon completion of well:	Blue CLAY	75	84
(1) Diameter: 2 inches.	LIGNITE	84	85
(2) Total Depth: 352 feet.	TRAC. OF BL. SAND & CLAY	85	92
(3) Water Level: 153 feet below top of ground.	ROCK	92	92 1/2
(4) Cased to 273, Size 2	Blue CLAY	92 1/2	110
(5) Screen: Size OPEN, Length	FINE SAND	110	126
(6) Were any formations sealed against pollution? SHAFT CAP AT 270' yes, no.	LIGNITE	126	130
If YES depth of formation	Blue CLAY & TRAC. SAND	130	147
Why	Blue CLAY	147	175
Drillers Remarks:	LIGNITE	175	178
	ROCK	178	268
	Blue CLAY	268	315
	CLAY	315	332
	TRAC. OF SAND	315	332
	MEDIUM COARSE SAND	332	352



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss