

CLAIBORNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

EX # 213 GN 01317

WATER WELL DRILLERS LOG


5-7-64

Date: 5-7-1964, Driller: Layne-Central Co. Cour: Claiborne

CODED

(1) Owner of Land: <u>Town of Port Gibson</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Port Gibson, Miss.</u> (Address)	top soil	2	2
(2) Location: <u>1/4, 1/4, Sec. 4 11^N 10^W R. 2E</u>	sandy clay	13	15
_____ miles _____ of _____ (distance) (direction) (Nearest Town)	blue clay	81	46
(3) Topography: _____ (Hilly) (Flat) (Level)	rock	2	48
(4) Purpose of Well: <u>municipal</u> (Domestic Irrigation Municipal, Industrial, Other)	clay-stks rock	17	65
Information upon completion of well:	rock	1	66
(1) Diameter <u>24</u> inches.	clay-stks rock	4	70
(2) Total Depth <u>203' 2"</u> feet.	hard clay	21	91
(3) Water Level <u>89</u> feet below top of ground.	rock	3	94
(4) Cased to <u>129' 10"</u> , Size <u>12"</u>	clay	4	98
(5) Screen: Size <u>10"</u> , Length <u>30'</u>	sand	12	110
(6) Were any formations sealed against pollution? <u>X</u> yes, _____ no.	clay	2	112
If YES depth of formation <u>129' 10"</u>	sand	3	115
Why _____ required	clay	3	118
Drillers Remarks: _____	sand	5	123
_____	clay	8	131
_____	sand	21	152
_____	clay	2	154
_____	sand	2	156
_____	clay	5	161
_____	rock	4	165
_____	clay	23	188
_____	fine sand - clay	4	192
_____	sand-medium	12	204

CODED



Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.