

MISSISSIPPI BOARD OF WATER COMMISSIONERS

6 CLARKE
D7
4-26-66

WATER WELL DRILLERS LOG

Date: 4-26, 1966, Driller: Mr. Donald Hill County Clarke

(Name)


(1) Owner of Land: J. C. DAVIDSON
(Name)
RT 7 MDN, MISS
(Address)
(2) Location: 1/4, 1/4, Sec. 5 T. R. 4N 17E
on Snell Road
1.8 miles S.E. of Mendota
(distance) (direction) (Nearest Town)
(3) Topography: HILLY
(Hilly) (Flat) (Level)
(4) Purpose of Well: DOMESTIC
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SAND + CLAY STR	0	130
H SHALE	130	145
BLK SANDY SHAL	145	153
ROCK	153	156
M TO H SHALE	156	168
BROWN SHALE LIG. SANDY	168	200
H SHALE	200	210
SOFT SHALE LIG. SANDY	210	235
M TO H SHALE	235	267
ROCK	267	269
M SHALE	269	293
SOFT SHALE	293	304
ROCK	304	305
SOFT TO M SHALE	305	320
SOFT SHALE SANDY	320	353
ROCK	353	355
H SHALE	355	382
ROCK	382	384
SOFT SHALE	384	392
SOFT SHALE TO SANDY SHAL	392	435

Information upon completion of well:

(1) Diameter 4 inches.
(2) Total Depth 435 feet.
(3) Water Level 175 feet below top of ground.
(4) Cased to 252, Size 4
(5) Screen: Size _____, Length _____
(6) Were any formations sealed against pollution?
_____ yes, _____ no.

If YES depth of formation _____
Why _____
Drillers Remarks: _____



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.