

CLARKE MISSISSIPPI BOARD OF WATER COMMISSIONERS

L 21  
7-62

L or M p

WATER WELL DRILLERS LOG

Date: July, 1962, Driller: Peoples & Rutledge County, Clarke

BOUEY

(Name)

(1) Owner of Land: Bouey  
(Name)  
Hannaway, Miss  
(Address)

(2) Location: 1/4, 2 N 4 E, Sec. 25 T. R.,  
Highway 13 E  
0 miles E, of Paducah  
(distance) (direction) (Nearest Town)

(3) Topography: Hilly  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
top to yellow sandy clay	18	18
yellow clay & sand	24	42
gray shale & sandstone	42	84
gray shale & sandy shale	52	136
white limst + limestone	69	205
white sand & brown shale streak	15	220
white sand	32	252


Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 252 feet.
- (3) Water Level 80 feet below top of ground.
- (4) Cased to 240, Size 2"
- (5) Screen: Size 2", Length 6'
- (6) Were any formations sealed against pollution?  
yes,  no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.