

GW14436

M36

Plugged and Abandoned


MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG 2

Date: August, 1966, Driller: Carloss Well Supply Co County: Clarke

(Name)

(1) Owner of Land: <u>Harmony Water Association, Inc.</u> (Name) <u>(Clarke County) Harmony, Miss.</u> (Address)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(2) Location: <u>SE 1/4, NW 1/4, Sec. 29 T. 15 R. E.</u> <u>5</u> miles <u>Southwest</u> , of <u>Quitman</u> (distance) (direction) (Nearest Town) <u>MISS.</u>	Red Clay	18	18
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	Streaks Sand & Soft Clay	18	36
(4) Purpose of Well: <u>Municipal</u> (Domestic Irrigation Municipal, Industrial, Other)	Black Clay	12	48
Information upon completion of well:	Hard Sandstone	9	57
(1) Diameter <u>10</u> inches.	Black Clay	13	70
(2) Total Depth <u>275</u> feet.	Hard, Fine, Grey Sand	14	84
(3) Water Level <u>103</u> feet below top of ground.	Dark, Brown, Hard Clay	49	133
(4) Cased to <u>227'-10"</u> , Size <u>10"</u>	Hard Sandstone	2	135
(5) Screen: Size <u>6"</u> , Length <u>40'-4"</u>	Clay	6	141
(6) Were any formations sealed against pollution? <u>X</u> yes, <u>no.</u>	Hard Sandstone & Clam Shells	7	148
If YES depth of formation <u>Casing cemented</u> its entire length <u>Standard Procedure</u> Why _____	Hard, Fine, Med. Sand and Clean Shells	8	156
Drillers Remarks: _____	Clay	3	159
_____	Hard, Blue, Sandy Clay & Clam Shells	24	184
_____	Fine, Muddy, Blue Sand, Hard Clam Shells	14	198
_____	Med. Sand, Hard, Fine	20	219'
_____	Loose, Med. Sand,	7	226
_____	Med. Grey Sand, Hard	23	249
_____	Med. Grey Sand	23	272
_____	Med., Coarse, Loose Sand	23	294
_____	Coarse Sand, Loose Strks	15	309
_____	Lignite	2	311
_____	Brown Lignite	6	317
_____	Coarse, Loose Sand	28	345
_____	Med. Coarse, Hard Sand	20	365
_____	Clay		
_____			
_____			
_____			
_____			
_____			
_____			



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.