

WATER WELL DRILLERS LOG

Date: July, 1962, Driller: Peeples & Rutledge County Clarke
 (Name)

(1) Owner of Land: Roy Little
 (Name)
Rt. 2 Shubita
 (Address)

(2) Location: SW 1/4, SW 1/4, Sec. 9 T14R15E
5 miles West of De Soto
 (distance) (direction) (Nearest Town)

(3) Topography: Flat
 (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Topsoil to Red Sandy clay</u>	<u>15</u>	<u>15</u>
<u>Red sand + clay streaks</u>	<u>27</u>	<u>42</u>
<u>Gray sand + gray shale streak</u>	<u>48</u>	<u>90</u>
<u>Gray shale</u>	<u>46</u>	<u>136</u>
<u>White & green limonite & lime</u>	<u>53</u>	<u>189</u>
<u>green limy shale</u>	<u>10</u>	<u>199</u>
<u>gray shale</u>	<u>11</u>	<u>210</u>
<u>white sand</u>	<u>23</u>	<u>233</u>

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 233 feet.


(3) Water Level 58 feet below top of ground.

(4) Cased to 227', Size 2"

(5) Screen: Size 2", Length 6'

(6) Were any formations sealed against pollution?
no

If YES depth of formation _____
 Why _____
 Drillers Remarks: Water is lightly colored yellowish



(Use Back Side)