


MISSISSIPPI BOARD OF WATER COMMISSIONERS
COAHOMA

B8 WATER WELL DRILLERS LOG

Coahoma

Date: 3/15, 1961, Driller: Bailey Drilling Co. County: Washington
(Name)

(1) Owner of Land:	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Pure Oil Co.</u> (Name)	<u>Clay</u>	<u>5</u>	<u>5</u>
<u>Friars Point, Miss.</u> (Address)	<u>Sand</u>	<u>57</u>	<u>62</u>
(2) Location: <u>1/4</u> , <u>1/4</u> , Sec. <u>11</u> T <u>24</u> R <u>4</u> W	<u>Gravel + Sand</u>	<u>68</u>	<u>130</u>
<u>4</u> miles <u>East</u> of <u>Friars Point</u> (distance) (direction) (Nearest Town)	<u>Mud</u>	<u>136</u>	<u>266</u>
(3) Topography: <u>Flat</u>	<u>Sand + Mud</u>	<u>21</u>	<u>287</u>
(4) Purpose of Well: <u>Domestic</u>	<u>Sand</u>	<u>61</u>	<u>348</u>
(Domestic Irrigation, Municipal, Industrial, Other)	<u>Mud</u>	<u>57</u>	<u>405</u>
Information upon completion of well:	<u>Rock</u>	<u>2</u>	<u>407</u>
(1) Diameter: <u>4 X 2</u> inches.	<u>Mud</u>	<u>7</u>	<u>414</u>
(2) Total Depth: <u>1158</u> feet.	<u>Sand</u>	<u>37</u>	<u>451</u>
(3) Water Level: <u>4</u> feet <u>above</u> ground.	<u>Mud + Sand</u>	<u>61</u>	<u>512</u>
(4) Cased to: <u>all way</u> Size <u>4 X 2</u>	<u>Sand</u>	<u>97</u>	<u>609</u>
(5) Screen: Size <u>2"</u> , Length <u>30 ft.</u>	<u>Mud</u>	<u>103</u>	<u>712</u>
(6) Were any formations sealed against pollution?	<u>Sand</u>	<u>28</u>	<u>740</u>
yes, <input checked="" type="checkbox"/> no.	<u>Rocks</u>	<u>10</u>	<u>750</u>
If YES depth of formation _____	<u>Mud + Sand</u>	<u>10</u>	<u>760</u>
Why _____	<u>Rocks</u>	<u>10</u>	<u>770</u>
Drillers Remarks: _____	<u>Mud</u>	<u>14</u>	<u>784</u>
	<u>Rocks</u>	<u>6</u>	<u>790</u>
	<u>Mud</u>	<u>14</u>	<u>804</u>
	<u>Rocks</u>	<u>6</u>	<u>810</u>
	<u>Mud + Sand</u>	<u>66</u>	<u>876</u>
	<u>Mud</u>	<u>179</u>	<u>1055</u>
	<u>Sand + Mud</u>	<u>20</u>	<u>1075</u>
	<u>Sand</u>	<u>87</u>	<u>1162</u>



Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.