

Coahoma
#E61
10-65

MISSISSIPPI BOARD OF WATER COMMISSIONERS

Not Permitted

WATER WELL DRILLERS LOG

CODED
Code

Date: 10-4-1965, Driller: Layne-Central Co. County Coahoma

(Name)

(1) Owner of Land: Coahoma Jr. College
(Name)
Clarksdale, Mississippi
(Address)
NW 1/4, SW 1/4, Sec. 7 T28 R44
(2) Location: NW 1/4, SW 1/4, Sec. 7 T28 R44
36
miles (distance) 36 (nearest Town)
(3) Topography: College
(Hilly) (Flat) (Level)
(4) Purpose of Well: College
(Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
sandy clay	15	0
coarse sand	60	15
sand-gravel	142	60
clay	224	142
sandy shale	302	224
mid. sand	390	302
coarse sand	431	390
fine sand-lignite	512	431
sahd-shale	604	512
sand	632	604
shale	687	632
sand	703	687
shale	727	703
rock	728	727
shale	734	728
rock	735	734
shale	745	735
rock	746	745
shale	768	746
rock	768	768
shale	823	769
rock	824	823
gumbo	847	824
rock	848	847
gumbo	851	848
hard rock	852	851
gumbo	857	852
hard rock	858	857
gumbo	902	858
rock	903	902
hard gumbo	920	903
continued on back		

Information upon completion of well:

(1) Diameter 8 inches.

(2) Total Depth 1854 feet.

(3) Water Level 16' feet below top of ground.

(4) Cased to 1801', Size 8"


(5) Screen: Size 6", Length 52' 4"

(6) Were any formations sealed against pollution?
X yes, no.

If YES depth of formation 1801'

Why required

Drillers Remarks: @ 130' of head
@ 260 8 hr.
1965 Turbine. 15 hp
8" (6 Stage)
1768 Gravel water b
TD 1854



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Mis.