

COAHOMA MISSISSIPPI BOARD OF WATER COMMISSIONERS

H 12

10-23-63 WATER WELL DRILLERS LOG

Date: 10/23, 1963, Driller: Railey Dr. Co. County: Washington
 (Name)

(1) Owner of Land: L.D. Brown
 (Name)
Rena Lara, Miss.
 (Address)

(2) Location: 1/4, 1/4, Sec 5, 3, 6, T26R5
3 miles East of Rena Lara
 (distance) (direction) (Nearest Town)

(3) Topography: Flat
 (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| Clay | | 18 |
| Sand | | 75 |
| Gravel | | 120 |
| Mud | | 422 |
| Sand | | 493 |
| Mud | | 574 |
| Sand + Mud | | 585 |
| Sand | | 666 |
| Mud | | 732 |
| Sand Gravel | | 873 |
| Mud | | 900 |
| Rocks every few feet | | 1159 |
| Mud | | 1398 |
| Sand | | 1452 |

Information upon completion of well:

(1) Diameter: 4 X 3 X 2 1/2 X 2 inches.

(2) Total Depth: 1452 feet.

(3) Water Level: 4 feet above top of ground.

(4) Cased: all way, Size: as above

(5) Screen: Size 2", Length 30 ft.


(6) Were any formations sealed against pollution?
 _____ yes, X no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____

Cased



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss