

Coahoma
H 25
12-67

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

12/4 1967 Bailey Drlg Co Coahoma
date well completed firm name county well located

LANDOWNER: Gordon Keith
Rena Lara
Miss.
(mailing address)


WELL LOCATION:
sec. 6 T. 26 N R. 5 W
1 miles E of Rena Lara
(distance) (direction) (nearest town)

WELL PURPOSE: home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:
(1) diameter (inches) 4 X 2 1/2 X 2
(2) total depth (feet) 1408
(3) static water level (feet) 3 below top of ground.
(4) casing Steel (material) (depth)
4 X 2 1/2 X 2 if telescope see back. (size)
(5) screen 20' 1388 (length) (depth to top)
2" Stainless Steel (size) (material)
(6) pump 1 10 (HP) (yield gpm)
Electric (type power)
(7) electric log No (yes or no)
(organization running log)
(8) how well bottom plugged back pressure valve

description of formations encountered	from	to
Clay	0	30
Sand	30	100
Gravel	100	140
Mud	140	420
Sand	420	480
Mud	480	650
Sand	650	690
Mud	690	870
Rocks	870	871
Mud	871	910
Rocks	910	911
Mud	911	990
Rocks	990	998
Mud	998	1019
Rocks	1019	1021
Mud	1021	1058
Rocks	1058	1061
Mud	1061	1070
Rocks	1070	1071
Mud	1071	1255
Sand	1255	1265
Mud + Sand	1265	1327
Mud	1327	1342
Sand	1342	1408

CODED



DRILLERS REMARKS: