

COAHOMA MISSISSIPPI BOARD OF WATER COMMISSIONERS

L 19

WATER WELL DRILLERS LOG

CODED

8-18-65

Date: 8-18, 1965, Driller: Fike County Farmers Union County Coahoma
(Name)

(1) Owner of Land: Rudy Carr
(Name)
Clarksdale, Miss
(Address)

(2) Location: 1/4, 1/4, Sec. 25 T26R4,
5 1/2 miles South of Clarksdale,
(distance) (direction) (Nearest Town)

(3) Topography: Flat
(Hilly) (Flat) (Level)

(4) Purpose of Well: Irrigation
(Domestic Irrigation
Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|-----------------------------------------------------------------------|------------------------|---------------|
| TOP SOIL | | 14 1/2 |
| MUD | 6 1/2 | 21 |
| Buckshot | 6 1/2 | 27 1/2 |
| Blue mud | 32 1/2 | 60 |
| Med to coarse sand | 19 1/2 | 79 1/2 |
| Med sand & large gravel | 13 | 92 1/2 |
| Med sand | 13 | 105 1/2 |
| Med sand & large rock & gravel | 6 1/2 | 112 |

Information upon completion of well:

(1) Diameter 14 inches.

(2) Total Depth 108 feet.

(3) Water Level 23 feet below top of ground.

(4) Cased to 60, Size 14"


(5) Screen: Size 14", Length 48

(6) Were any formations sealed against pollution?
_____ yes, _____ no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



CODED

[Handwritten signature]

(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.