

Coahoma  
M 8  
9-59

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

11/4/66  
760

Date: Sept. 28, 1959, Driller: Layne-Central Company County Coahoma

(Name)

(1) Owner of Land: Adams Gin Company

(Name)

Clarksdale, Mississippi

(Address)

(2) Location: 1/4, 1/4, Sec. 17 T26R3

       miles        of Claremont  
(distance) (direction) (Nearest Town)

(3) Topography: flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: industrial  
(Domestic Irrigation  
Municipal, Industrial, Other)

| Description & Color of Materials<br>Sand, Clay, Red Clay, Shell, etc. | Thick-<br>ness<br>Feet | Depth<br>Feet |
|---|------------------------|---------------|
| Clay  | 12                     | 12            |
| Fine sand   | 46                     | 58            |
| Coarse sand   | 7                      | 65            |
| Coarse sand & pea gravel  | 86                     | 151           |
| Coarse sand   | 39                     | 190           |
| Sandy shale   | 40                     | 230           |
| Hard shale  | 102                    | 332           |
| Sandy shale   | 53                     | 385           |
| Sand  | 32                     | 417           |
| Sandy shale   | 21                     | 438           |
| Hard shale  | 92                     | 530           |
| Clay - gummy  | 88                     | 618           |
| Shale   | 32                     | 650           |
| Hard shale  | 43                     | 693           |
| Rock  | 1                      | 694           |
| Hard shale  | 36                     | 730           |
| Rock  | 1                      | 731           |
| Clay  | 29                     | 760           |
| Rock  | 1                      | 761           |
| Sandy shale   | 39                     | 800           |
| Hard shale  | 25                     | 825           |
| Rock  | 1                      | 826           |
| Sandy shale   | 69                     | 895           |
| Clay  | 25                     | 920           |
| Sandy shale   | 29                     | 949           |
| Hard shale  | 36                     | 985           |
| Sandy shale   | 75                     | 1060          |
| Shale   | 120                    | 1180          |
| Sand; strks. shale  | 53                     | 1233          |
| Shale   | 8                      | 1241          |
| Sand  | 34                     | 1275          |

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 1275 feet.

(3) Water Level 4 feet below top of ground.

(4) Cased to 1241', Size 4"

(5) Screen: Size 4", Length 30'

(6) Were any formations sealed against pollution?


yes yes,        no.

If YES depth of formation Packer above the screen and B.P.V.

Why

Drillers Remarks:

40 GPM.



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.