

Copied
D 31
10-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

CODED

Date: Oct. 3, 1966 Driller: Burney Water Well Service, Inc., Copiah County

(1) Owner of Land: Earl Martin
(Name)
215 1/2 W. RR. Ave. Crystal Springs
(Address)

(2) Location: NE 1/4, NE 1/4, Sec 8, T2N, R2W
5 miles N-West of Crystal Spgs.
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic, Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Top soil & clay	6	6
Red sand & big gravel	30	36
Red sand & clay	8	44
Gravel	22	66
Pipe clay & red sand	16	82
Red sand & clay	19	101
Pea gravel	33	134
Rock	1/2	134 1/2

Information upon completion of well:

(1) Diameter 4" inches

(2) Total Depth 134 1/2 feet

(3) Water Level 112 feet below top of ground

(4) Cased to 129' Size 2"


(5) Screen: Size 2" Length 5'

(6) Were any formations sealed against pollution?
 yes, no

If YES depth of formation From surface

Why to prevent surface pollution

Drillers Remarks: Sanitary well seal used



Well No.

(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.