

Copied
D 32
12-66

D 28
Well No 2
S.E. 1/4
M.G. 5

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

Date: Dec. 22, 1966 Driller: Burney Water Well Service, Inc. Copiah
(When well drilled) (Name) (Where well is located)

COMMUNITY WELL NO. 2

(1) Owner of Land: Samuel McNeil
(Name)
Crystal Springs, Miss.
Deas Road (Address)

(2) Location: SW 1/4, NE 1/4, Sec 23, T2N R2W,
1/2 miles West of Crystal
(distance) (direction) (Name of Springs)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal
(Domestic Irrigation
Municipal Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay & Sand Gravel	58	58
Sand stone or rock	1	59
Water sand & pea gravel	16	75
Hard rock	3	78
Blue clay	12	90
Sand & clay layers	15	105
all fine blue sand	21	126
Rock	1	127
Hard blue & Grey Shale	13	140

Information upon completion of well:

(1) Diameter 6 inches

(2) Total Depth 140 feet

(3) Water Level 54 feet below top of ground

(4) Cased to 107' Size 4"

(5) Screen: Size 4" Length 19'

(6) Were any formations sealed against pollution?
X yes, no

If YES depth of formation 140' cement in


Why to prevent surface pollution

Drillers Remarks: Well seal used

Yield in gpm: 30

Size pump: 1 1/2 h.p.

Type power: Electric



Mail this copy to Board of Water Commissioners 429 Miss. Jackson, Miss.