

WATER WELL DRILLERS LOG

CODED

Date: Nov. 19 1962 Driller: Burney Water Well Serv Co. Copiah
 307 5451 6807 6811 (Name)

(1) Owner of Land: Richard Jackson
(Name)

Crystal Springs, Miss.
(Address)

Dear Road
(Address)

(2) Location: 1/4 Sec 9 T. 10 N. R. 12 E.
(1/4 Sec. T. R. S.)

4 miles North of Crystal Springs
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic, Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thickness Feet	Depth Feet
Red top soil	8	8
Yellow & grey clay	18	26
Layers yellow sand	10	36
Hard blue & grey shale	34	70
Fine sand layers	20	90
Blue clay	15	105
Blue & yellow formation	11	116
Fine blue sand layers	22	138
Hard shale	4	142

Information upon completion of well

(1) Diameter: 6 inches

(2) Total Depth: 142 feet

(3) Water Level: 35 feet below top of ground

(4) Cased to: 130' Size: 4"

(5) Screen: Size: 4" Length: 1'


(6) Were any formations sealed against pollution?
 yes no

If YES depth of formation: From Surface

Why: to prevent surface pollution

Drillers Remarks: Used sanitary well seal

CODED



(Use Back Side)

Well No.