

COPIAH MISSISSIPPI BOARD OF WATER COMMISSIONERS


E 22
12-28-60

WATER WELL DRILLERS LOG

M.H.L.
E 22 CODED

Date: Dec. 28, 1960, Driller: Barclay Keller, (Cell No. 1) Jones County, Georgia
(Ben Barclay & Son)

(1) Owner of land: <u>Fisher, Mrs. Rest. Baptist</u> (Name)	Drill Pipe & Coll. or Material Ch. Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(2) Location: <u>Old Georgetown Road</u> E 500 ft. S 1/2 Sec. 16 T. 12 N. R. 10 W.	Tops oil & clay	12	12
5 miles NE of Ocala, FL (distance) (direction) (Nearest town)	Clay & sand gravel	51	63
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	Blue/grey clay	51	94
(4) Purpose of Well: <u>Domestic</u> (Domestic, Irrigation, Municipal, Industrial, Other)	Rock	9	103
Information upon completion of well:	Layers fine sand & clay	7	110
(1) Diameter: <u>4</u> inches	Blue clay	14	124
(2) Total Depth: <u>316</u> feet	Rock	4	128
(3) Water Level: <u>179</u> feet below top of ground	Hard blue clay	46	174
(4) Cased to: <u>316</u> Size: <u>2"</u>	Soft brown formation	12	186
(5) Screen Size: <u>2"</u> Length: <u>5</u> ft.	Limestone	26	212
(6) Were any formations sealed against pollution? <u>no</u>	Layers fine sand	3	215
If YES depth of formation: <u>From surface</u>	Blue shale	74	289
Why: <u>No relevant surface pollution</u>	Rock & sand layers	11	300
Drillers Remarks:	Good Sand	6	306
	Rock	1	307
	Good sand	7	314
	Blue clay	2	316



Well No

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss