


COPIAH MISSISSIPPI BOARD OF WATER COMMISSIONERS

H 2001
6-9-65

WATER WELL DRILLERS LOG

Date: June 9, 1965, Driller: Ben Burney, County: Copiah

(1) Owner of Land: <u>George Mims</u> (Name)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Rt. 2, Box 174</u> (Address)	Top soil & clay	18	18
<u>Dentville Road</u>	Fine white sand	3	21
(2) Location: <u>1/4</u> Sec. <u>13W</u> T. <u>3</u> R. <u>3</u>	Pipe clay	9	30
<u>3</u> miles <u>East</u> of <u>Dentville</u> (distance) (direction) (Nearest Town)	Black gumbo	31	61
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	Rock	3	64
(4) Purpose of Well: <u>Domestic</u> (Domestic Irrigation, Municipal, Industrial, Other)	Tight blue clay	20	84
Information upon completion of well:	Rock	2	86
(1) Diameter <u>4 1/2</u> inches.	Clay & Sand layers	10	96
(2) Total Depth <u>205</u> feet.	Fine Sand	3	99
(3) Water Level <u>60</u> feet below top of ground.	Rock	1	100
(4) Cased to <u>193'</u> , Size <u>2"</u>	Clay	22	122
(5) Screen: Size <u>2 1/2"</u> , Length <u>5"</u>	All Sand	18	140
(6) Were any formations sealed against pollution? <u>X</u> yes, <u> </u> no.	Shale	7	147
If YES depth of formation <u>From Surface</u>	Rock	1	148
Why To <u>prevent surface pollution</u>	Layers of Sand & Clay	32	180
Drillers Remarks:	All Medium blue sand	25	205



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.