

Copiah  
J40  
10-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

MBS  
J40

WATER WELL DRILLERS LOG

MODEL

Inc.

Date: Oct. 3, 1966, Driller: Burney Water Well Service, Inc. County: Copiah

(Name)

(1) Owner of Land: Roy Miller

(Name)

R. F. D. Hazlehurst

(Address)

(2) Location: SW 1/4, SW 1/4, Sec. 30, T1N R2W

3 miles N west of Hazlehurst  
(distance) (direction) (Nearest Town)

(3) Topography: Hilly

(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic

(Domestic Irrigation  
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 4" inches.

(2) Total Depth 142 feet.

(3) Water Level 122 feet below top of ground.

(4) Cased to 137", Size 2"

(5) Screen: Size 2", Length 5"

(6) Were any formations sealed against pollution?

X yes, no.

If YES, depth of formation From surface


Why to prevent surface pollution

Drillers Remarks: Sanitary well seal used

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red Sand	22	22
Gravel & sand	25	47
Big Gravel	18	65
Pea Gravel & Rock	37	102
Pipeclay & gravel	28	130
Pea Gravel	6	136
Coarse water sand	6	142

Elev 430 Top

MODEL



Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.