

MISSISSIPPI BOARD OF WATER COMMISSIONERS

P 37

WATER WELL DRILLERS LOG

12-30-65

Date: 12/30/1965, Driller: Burrey Well Service, Inc. County: Copiah

E Log # 72


(1) Owner of Land: Fred Banks  
 (Name)  
Route 3 South, Hazlehurst  
 (Address)  
Old Hwy 51  
 (2) Location: 1/4, 1/4, Sec 16 T10R2  
2 miles South of Hazle  
 (distance) (direction) (Nearest Town)  
 (3) Topography: Hilly  
 (Hilly) (Flat) (Level)  
 (4) Purpose of Well: Domestic  
 (Domestic Irrigation, Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter: 4 inches.  
 (2) Total Depth: 382 feet.  
 (3) Water Level: 178' feet below top of ground.  
 (4) Cased to: 297' Size 2"  
 (5) Screen: Size 2" Length 5'  
 (6) Were any formations sealed against pollution?  
X yes,        no.

If YES depth of formation From Surface  
 Why To prevent surface pollution  
 Drillers Remarks: Sanitary Well seal  
used

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Top soil & gravel	12	12
Red Sand	6	18
Fine Gravel	4	22
Pipe Clay	8	30
Sand layer	3	33
Pipe clay	8	41
Tight gray clay	15	56
Hard shale & gray clay	29	115
Fine sand	10	125
Soft sandy formation	17	142
Fine sand	5	147
Shale	6	153
Fine sand layers	8	162
Grey clay	8	170
Hard gray formation	20	190
Hard tight sand	26	216
Loose layers of sand	31	247
Grey & blue shale	21	268
Hard grey formation	13	282
Fine sand in layers	12	294
Rock layers	2	296
Shale	29	325
Soft sandy formation	19	344
Gumbo or clay	38	382



Well No

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.