

MISSISSIPPI BOARD OF WATER COMMISSIONERS

COPIAH

S 8


WATER WELL DRILLERS LOG

8-12-64

Date: Aug. 12, 1964, Driller: BURNEY WATER WELL SERV. County: COPIAH

(Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>Frances Del Rosso</u> (Name)	Top soil and clay	16	16
Box 74, Pattison, Mississippi	Sand rock	3	19
(On highway <u>547</u> )	Yellow clay	3	22
(2) Location: <u>SE 1/4, NW 1/4, Sec. 5 T9 R5</u>	Grey clay	12	34
<u>20</u> miles <u>West</u> , of <u>Hazlehurst</u> , (distance) (direction) (Nearest Town)	Sand rock layers	4	38
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	Lime stone	11	49
(4) Purpose of Well: <u>Domestic</u> (Domestic Irrigation Municipal, Industrial, Other)	Blue or grey shale	5	54
Information upon completion of well:	Lime stone	6	60
(1) Diameter <u>4 1/2</u> inches.	Layers shale and rock	10	70
(2) Total Depth <u>139</u> feet.	Grey shale	12	82
(3) Water Level <u>114</u> feet below top of ground.	Sand layers	10	92
(4) Cased to <u>131</u> , Size <u>2"</u>	Rock	3	95
(5) Screen: Size <u>2 1/2</u> , Length <u>5'</u>	Grey shale	4	99
(6) Were any formations sealed against pollution? <u>X</u> yes, _____ no.	Sand layers	11	110
If YES depth of formation <u>80'</u> from surface.	Soft shale <u>CODED</u>	25	135
Why <u>To prevent surface pollution</u>	Sand strata	16	151
Drillers Remarks:	Blue shale	1	152



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners, 429 Miss. St. Jackson, Miss.