


MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
Office of Land and Water Resources
P. O. Box 2309
Jackson, MS 39225
Water Well Plugging/Decommissioning Form
OLWR-DF-1 (04/08)

COUNTY WELL LOCATED: Desoto		WELL NUMBER: 9 E GRID	
PERMIT NUMBER: MS-GW-16752		DATE WELL PLUGGED: 8-31-2011	
NAME OF FIRM PLUGGING WELL: Chris Hill Construction Company LLC.		TELEPHONE NUMBER: 901-767-6312	
NAME AND ADDRESS OF CURRENT LANDOWNER: Desoto County Regional Utility Authority			
WELL LOCATION: sw1/4 of the sw1/4 SECTION: 08 TOWNSHIP: 02S RANGE: 09W			
WELL LOCATION: LATITUDE: LONGITUDE: METHOD (CIRCLE ONE): (1) USGS QUAD (2) CONVENTIONAL SURVEY (3) GPS - HAND HELD OR SURVEY GRADE			
DISTANCE: DIRECTION: NEAREST TOWN: OTHER LANDMARK:			
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): Dewatering for a construction project.			
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL: Mersino Dewatering			
NAME OF LANDOWNER WHEN WELL WAS DRILLED: Desoto County Regional Utility Authority			

WELL DATA			
WELL DEPTH: 100 feet		HOLE DEPTH: 100 feet	
CASING DIAMETER (IN.): 12	CASING LENGTH (FT.): 100	TYPE OF CASING: Steel	
DEPTH TO STATIC WATER LEVEL: 15 feet		DATE WELL COMPLETED: 8-9-2010	
WHY IS THE WELL BEING ABANDONED? The dewatering portion of the project is finished.			

<p>DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE, MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING MATERIAL, ETC.)</p> <p>The well casing and screen was removed by using a vibratory hammer and a crane. The hammer vibrated the casing while the crane pulled the casing vertically out of the ground.</p> <p>The casing and screen was completely removed.</p> <p>Natural ground had filled the casing hole to approximately 2 to 3 feet below the existing ground. This hole was filled with Bentonite and compacted.</p>
--

I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS.	
Shannon McCarley	
 SIGNATURE	MS LICENSE NUMBER 9-12-2011 DATE

RECEIVED
SEP 16 2011
BY: OLWR

