

Desoto  
F40  
12/67

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

**CODED**

WATER WELL DRILLERS LOG

12-14-1967 date well completed  
Watson Co. firm name  
Desoto county well located

LANDOWNER: Reese - Frueby  
Land Co. 2700 Poplar  
Memphis Tenn.  
(mailing address)

WELL LOCATION:  
sec. 12 T. 2 N. R. 8 E.  
4 miles S of Southaven  
(distance) (direction) (nearest town)

WELL PURPOSE: farm  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4"

(2) total depth (feet) 319

(3) static water level (feet) 130 below top of ground.

(4) casing steel pipe 302' 19"  
(material) (depth)  
If telescope see back.  
(size)


(5) screen 16' 7"  
(length) (depth to top)  
.008 Stainless Steel  
(size) (material)

(6) pump 2 26  
(HP) (yield gpm)  
Electric  
(type power)

(7) electric log \_\_\_\_\_  
(yes or no)  
(organization running log)

(8) how well bottom plugged \_\_\_\_\_

description of formations encountered	depth	
	from	to
Surge clay	0	20
Red Sandy Clay	20	31
Rock	31	32
yellow clay	32	50
Fine Medley Sand	50	130
Med Course Sand	130	141
Clay w/ sand shls.	141	177
Blue clay	177	178
Rock	178	205
Blue clay	205	206
Rock	206	212
Blue clay	212	213
Rock	213	218
Blue clay	218	219
Rock	219	224
Blue clay	224	225
Hard Rock	225	254
Clay & sand shls.	254	255
Fine Sand	255	266
Fine to Med. Sand	266	280
Fine med cone	280	295
Course sand	295	319
Soft Sand	319	320



DRILLERS REMARKS: