

Desoto MISSISSIPPI BOARD OF WATER COMMISSIONERS

EG20

5-66

WATER WELL DRILLERS LOG

CODED

Date: 5-27-, 1966, Driller: Layne-Central Co., County Desoto
(Name)

(1) Owner of Land: Brights Water Assn.
(Name)
Hernando, Mississippi
(Address)

(2) Location: 1/4, NE 1/4, Sec. 34 T. 2 R. 7 S
miles of
(distance) (direction) (Nearest Town)

(3) Topography:
(Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red clay	25	25
sand-gravel	5	30
hard blue clay	36	66
rock	1	67
tough clay	49	116
sandy clay	67	183
fine sand-shale	17	200
sand	6	206
pk. sand	22	228
pk. sand	22	250
pk. sand	21	271
clay-sand	6	277

Information upon completion of well:

(1) Diameter 8 inches.

(2) Total Depth 277 feet.

(3) Water Level 128 feet below top of ground.

(4) Cased to 234', Size 8"

(5) Screen: Size 6", Length 30'


(6) Were any formations sealed against pollution?
X yes, no.

If YES depth of formation 234'

Why required

Drillers Remarks:

CODED



Well No.

(Use Back Side)

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.