

Forrest  
A 24  
3-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS


USGS Files

WATER WELL DRILLERS LOG

Date: 3-16-1966, Driller: Carloss Well Supply County Forrest

(Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>Rawls Springs</u> (Name) <u>Utility Association, Inc.</u>	Top Soil	2	2'
	Hard Brown Clay	48	50'
(2) Location: <u>Rawls Springs, Mississippi</u> (Address) <u>1/4, 21 1/4, Sec. 14, T. 14 N., R. 14 W.</u> Forrest County, Hattiesburg, Miss. miles _____, of _____ (distance) (direction) (Nearest Town)	Hard Blue Shale	36	86'
	Shale with Streaks Sand	31	117'
	Sand with Small Gravel	26	143'
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	Sand	5	148'
	Coarse Sand and Gravel	30	178'
(4) Purpose of Well: <u>Municipal</u> (Domestic Irrigation Municipal, Industrial, Other)	Coarse Sand and Gravel	22	200'
	Hard Clay	38	238'
	Shale, Lignite Streaks	61	299'
	Coarse Sand and Gravel	61	360'
Information upon completion of well:	Sand with Thin Strks. Shl.	31	391'
(1) Diameter <u>8</u> inches.	Coarse Sand	59	450'
(2) Total Depth <u>705'-9"</u> feet.	Sand w/ Thin Strks. Lignite	30	480'
(3) Water Level <u>86</u> feet below top of ground.	Hard Sandy Shale	25	505'
(4) Cased to <u>660'</u> , Size <u>8"</u>	Sand	5	510'
(5) Screen: Size <u>6"</u> , Length <u>40'</u>	Hard Clay w/ Strks. Sand	92	602'
(6) Were any formations sealed against pollution? Yes <input checked="" type="checkbox"/> yes, <input type="checkbox"/> no.	Hard Clay	31	633'
If YES depth of formation <u>Casing cemented</u> its entire length.	Broken Strks Sand, Clay	19	652'
Why <u>Standard Procedure</u>	Hard Clay	3	655'
Drillers Remarks:	Fine Sand	15	670'
	Medium Sand	32	702'
	Sand, Thin Streaks Shale	13	715'
	Shale	12	727'
	Sand, Thin Strks. Shale	5	732'
	Shale, Thin Streaks Sand	29	761'
	Streaks Sand, Shells, Clay	34	795'



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss