

FORREST MISSISSIPPI BOARD OF WATER COMMISSIONERS

D 38

③

USGS File


9-21-65

WATER WELL DRILLERS LOG

D 38

Date: 9-21-, 1965, Driller: Layne-Central Co. County Forrest
(Name)

(1) Owner of Land: <u>Hercules Powder Co.</u> (Name) <u>Hattiesburg, Miss.</u> (Address)	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. thickness	Thickness	Depth Feet
	top soil	3	0-3
	pipe clay	187	3-190
	shale	50	190-240
	fine sand-stks		
	shale	29	240-269
	sand	22	269-291
	shale, stks sand	71	291-362
	sand	138	362-500
	hard shale	28	500-528
	sand-shale	57	528-585
	sand	105	585-690
	shale	15	690-705
Information upon completion of well:			
(1) Diameter <u>18</u> inches.			
(2) Total Depth <u>687</u> feet.			
(3) Water Level <u>24</u> feet below top of ground.			
(4) Cased to <u>591'</u> , Size <u>18"</u>			
(5) Screen: Size <u>10"</u> , Length <u>70'</u>			
(6) Were any formations sealed against pollution?			
<u>X</u> yes, <u> </u> no.			
If YES depth of formation <u>591'</u>			
Why <u> </u> required			
Drillers Remarks:			



Well No.

Mail this copy to Board of Water Commissioners, 449 Miss. St. Jackson, Miss.