

Well no. 4.

Greene
K 4
XO + -68

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

Oct 1, 1968 Haertel's Well Service Greene
date well completed firm name county well located

LANDOWNER: L. O. Turner
Seabersville, Miss

(mailing address)

WELL LOCATION:


sec. 25 T. 3 (N) R. 7 E
S (W)
6 miles NW of Seabersville
(distance) (direction) (nearest town)

WELL PURPOSE: home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2 inches
- (2) total depth (feet) 179 ft.
- (3) static water level (feet) 7 1/2 ft. below top of ground.
- (4) casing P.V.C. 169 ft.
(material) (depth)
(size) if telescope see back.
- (5) screen 10 ft. 169 ft.
(length) (depth to top)
2" x 10" P.V.C. plastic
(size) (material)
- (6) pump 1 hp 5 gpm
(HP) (yield gpm)
electric
(type power)
- (7) electric log no
(yes or no)
(organization running log)
- (8) how well bottom plugged with
2" wash valve

description of formations encountered	from	to
<u>red clay</u>	<u>0</u>	<u>10</u>
<u>sand (med to coarse)</u>	<u>10</u>	<u>27</u>
<u>clay (yellow & white)</u>	<u>27</u>	<u>75</u>
<u>sand (fine & silty)</u>	<u>75</u>	<u>76</u>
<u>sandy clay</u>	<u>76</u>	<u>83</u>
<u>clay (hard grey)</u>	<u>83</u>	<u>101</u>
<u>sandy clay</u>	<u>101</u>	<u>106</u>
<u>sand with clay streaks</u>	<u>106</u>	<u>122</u>
<u>clay</u>	<u>122</u>	<u>124</u>
<u>sand (fine with clay chunks)</u>	<u>124</u>	<u>133</u>
<u>clay</u>	<u>133</u>	<u>138</u>
<u>sand & clay (mixed)</u>	<u>138</u>	<u>150</u>
<u>coarse sand</u>	<u>150</u>	<u>179</u>



DRILLERS REMARKS: well
yielded 18 gpm with
pump on rig