

C47

10-8-65

WATER WELL DRILLERS LOG

**CODED**

Date: Oct. 8, 1965, Driller: Walter Peniston County Hancock

(Name)

(1) Owner of Land: J. T. Flemming  
 Route, Picayune, Miss  
(Name)  
 (Address)

(2) Location: 1/4, 1/4, Sec. 22 T. 6 R. 6 E.  
4 miles East of Picayune  
(distance) (direction) (Nearest Town)

(3) Topography: Flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Yellow clay	33	0 to 33
White Sand	23	56
Blue clay	184	240
Grey sand	42	282
Blue clay	188	470
Grey sand	98	568
Blue clay	100	668
Soft Blue clay	107	775
Grey sand	20	795
Blue clay	190	985
Grey sand	95	1080
Soft Blue clay	42	1122
Grey sand & gravel	83	1205
Blue clay	203	1408
Grey sand		1469


Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 1469 feet.
- (3) Water Level Flow feet below top of ground.
- (4) Cased to \_\_\_\_\_, Size \_\_\_\_\_.
- (5) Screen: Size 012, Length 20'.
- (6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes, \_\_\_\_\_ no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_

Drillers Remarks: 15 1/2 lbs  
shut in at ground  
level

**CODED**



(Use Back Side)

Well No.

Handwritten notes at the top of the page, including the word "Introduction" and other illegible text.

Main body of handwritten text on the left side of the page, appearing to be a list or series of notes.

Handwritten text on the right side of the page, including the word "Conclusion" and other illegible text.

Handwritten text at the bottom right of the page, possibly a signature or date.

Handwritten text at the very bottom of the page, including the word "References" and other illegible text.