

HANCOCK
 H-7443
 Flus #81
 1/80

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

1980 G. RIVER DRILLING SERVICE HANCOCK

date well completed

firm name

county well located

LANDOWNER:	description of formations encountered	from	to
CENTER CONSTRUCTION CO. (ARMY AMMUNITION PLANT)	CLAY	0	21
WELL NO. 1	SAND + GRAVEL, COARSE	21	117
(mailing address)	CLAY	117	234
WELL LOCATION: SEA NW/4 NW/4	SAND	234	316
sec. 4 T. 8 N. R. 16 E. (S) (W)	CLAY and SAND STREWS	316	412
(distance) miles (direction) of (nearest town)	CLAY	412	496
	SAND (fine to medium)	496	686
	CLAY	686	755

WELL PURPOSE:
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 20
- (2) total depth (feet) 688
- (3) static water level (feet) 2 (below/above top of ground)
- (4) casing steel 493' (material) (depth)
- 20" (size) If telescope see back steel
- (5) screen 185' (length) 503' (depth to top)
- 10" (size) 304 S.S. (016) (material)
- (6) pump 150 (HP) 1200 (yield gpm)
- Elect. (type power)
- (7) electric log Yes (yes or no)
- Miss. Geol. Survey (organization running log)
- (8) how well bottom plugged BACK WASH VALUE

CODEE

Top of 10" LAP-403'
 LAP pipe - 100 ft. includes stringers
 20 ft. on top of screen.
 Bot. of string 693 ft.

DEPT. OF NATURAL RESOURCES
 BUREAU OF LAND & WATER RESOURCES


JUL 22 1980
 RECEIVED

DRILLERS REMARKS:

If well telescopes please sketch and show depths.

GROUND LEVEL

4 493 20"



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.