

HANCOCK

L 27

3-25-66

13V

MISSISSIPPI BOARD OF WATER COMMISSIONERS

CODED

WATER WELL DRILLERS LOG

Date: 3-25, 1966, Driller: Jutter West Works County Hancock
(When well drilled) (Name) (Where well is located)

(1) Owner of Land: Pearlington School
(Name)
Pearlington Miss.
(Address)
(2) Location: SW 1/4, NE 1/4, Sec. 16 T9S R 16 W
1 miles E of Pearlington
(distance) (direction) (Nearest Town)
(3) Topography: flat
(Hilly) (Flat) (Level)
(4) Purpose of Well: School
(Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay - sand streaks	48	48
sand - some gravel	51	99
Clay	12	111
sand	15	126
Clay	113	239
sand	34	273
Clay	99	372
sand	12	384
Clay	17	401
sand	119	520

CODED

Information upon completion of well:


(1) Diameter 4x6 inches.
(2) Total Depth 520 feet.
(3) Water Level + 6 feet above ground.
(4) Cased to all, Size 4" TOP 149' 26"
(5) Screen: Size 2 1/2", Length 40'
(6) Were any formations sealed against pollution?
yes, no.

If YES depth of formation 100 feet

Why required

Drillers Remarks:

Yield in gpm: 150
Size pump: 1 1/2 HP
Type power: elec.



[Faint, illegible handwriting throughout the page, possibly bleed-through from the reverse side.]

100
200
300
400
500
600
700
800
900
1000

[Faint, illegible handwriting in the right-hand column, possibly bleed-through from the reverse side.]