

HAR.
C 50
12-63

MISSISSIPPI BOARD OF WATER COMMISSIONERS

N510607 (20)

WATER WELL DRILLERS LOG

CODED

Date: Dec, 1963, Driller: Joe Miller County Harrison
(Name)

(1) Owner of Land: J.A. Smith
(Name)
RPH Sulfport Miss
(Address)

(2) Location: 1/4, 1/4, Sec. 19 5 11 T R
15 miles North, of Sulfport
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic Egg Farm
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Dark Clay & Red Clay</u>	<u>25</u>	<u>25</u>
<u>White Clay</u>	<u>35</u>	<u>60</u>
<u>Blue Clay</u>	<u>170</u>	<u>230</u>
<u>Fine Gray Sand W/G</u>	<u>16</u>	<u>246</u>
<u>Blue Clay</u>	<u>32</u>	<u>278</u>
<u>Gray Sand (Fine)</u>	<u>6</u>	<u>284</u>
" " "	<u>10</u>	<u>294</u>
" " <u>Sand</u>	<u>12</u>	<u>306</u>
" " "	<u>10</u>	<u>316</u>

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 316 feet.

(3) Water Level 44 feet below top of ground.

(4) Cased to 306, Size 2


(5) Screen: Size 2", Length 10'

(6) Were any formations sealed against pollution?
_____ yes, no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



CODED

Drill in Sand.

this sand runs to 380' feet have made two wells in this formation in last 16 yrs. but takes the hole off pipe in 5-6 years and continue water to wash in need to sell conditions but customer doesn't go along with suggestion

(Use Back Side)

Well No.

1900

Handwritten notes in the upper left quadrant, including the number '1900' and several lines of illegible cursive text.

Handwritten notes in the upper right quadrant, including the number '1900' and several lines of illegible cursive text.

Handwritten text 'Punch' with a small circle next to it, located in the middle right section of the page.

Handwritten text 'After 49' written vertically in the center of the page.

Handwritten text 'Blue Ridge' written vertically on the left side of the page.

Handwritten text 'Blue Ridge' written vertically at the bottom of the page.

